

Information to be included in all Legislation authorizing entering into a Contract:

1. The names, contract compliance no., location by City/State and status of all companies submitting a competitive bid or submitting an RFP or RFSQ.

| <u>Name</u> | <u>C.C. No.</u> | <u>City/State</u> | <u>Maj/MBE/FBE</u> |
|--------------------------|------------------------|--------------------------|---------------------------|
| Korda/Nemeth Engineering | 31-0922991 | Columbus, Oh | Majority |
| EMH&T, Inc. | 31-0685594 | Columbus, Oh | Majority |
| M-E Companies | 31-1442777 | Westerville/Ohio | Majority |

2. Complete address, contact name and phone number for the successful bidder only.

Korda/Nemeth Engineering
1650 Watermark Drive
Columbus, Ohio 43215
614-487-1650
Contact: John Panovsky,P.E.

3. A full description of all work to be performed including a full description of work to be performed during any known phasing of the contract.

This project consists of preparing detailed engineering plans that are suitable for bidding and constructing various waterline improvements. The five locations and work descriptions are described below.

1. Construct a 6-inch water main in Foster Street from the existing 6-inch water main in Northridge Road to the existing 6-inch water main in Blenheim Road. Transfer all existing taps to the new water main and abandon the existing 2-inch water main. (Approximately 300 feet)
2. Transfer all existing taps from the existing 2-inch water main in Glenmont Place, between Glenmont Avenue and Canyon Drive, to the existing 8-inch water main. Abandon the existing 2-inch water main.
3. Construct an 8-inch water main, including fire hydrants, in Lenappe Drive from the existing 8-inch water main in Overbrook Drive to a proposed 8-inch water main in Canyon Drive North. Transfer all existing taps to the new water main and abandon the existing 8-inch water main. (Approximately 1,350 feet)
4. Construct an 8-inch water main, including fire hydrants, in Canyon Drive from Sharon Avenue east to the intersection of Canyon Drive North and Canyon Drive. Transfer all existing taps to the new water main and abandon the existing 8-inch water main. (Approximately 2,400 feet)
5. Construct an 8-inch water main, including fire hydrants, in Overbrook Drive from Cooke Road to Yaronia Drive. Then from Yaronia Drive to Wynding Drive. Transfer all existing taps to the new water main and abandon the existing water mains. (Approximately 1,600 feet)

4. **A narrative timeline for the contract including a beginning date, beginning and ending dates for known phases of the contract and a projected ending date.**

The design portion of this Contract will be 515 days after the date of the Agreement is signed. The Record Drawing portion (less than 5% of the total job) will be completed after the construction has been completed.

5. **An estimate of the full cost of the Contract including a separate estimate of any and all phases or proposed future contract modifications.**

\$181,700.00