

- NOTES:
- ACCESS PATHS SHALL BE STRICTLY FOLLOWED AND ENFORCED. THEY HAVE BEEN SURVEYED TO AVOID SENSITIVE ENVIRONMENTAL AREAS IN THE PROJECT AREA.
  - THE CONTRACTOR SHALL INCLUDE IN THEIR BID FOR ITEM 623 CONSTRUCTION LAYOUT STAKES THE COST REQUIRED TO SURVEY AND STAKE THE EXISTING EASEMENTS, CITY ROW, PRIVATE PROPERTY LINES AND WETLANDS IN ORDER TO COMPLETE ALL SEWER REHABILITATION WORK AND CONSTRUCT BYPASS LINE. ALSO TO BE INCLUDED IS THE COST TO SURVEY AND STAKE ACCESS PATH BOUNDARIES AND TREES TO BE REMOVED.
  - CONTRACTOR SHALL USE THE ACCESS PATHS IDENTIFIED ON THE DRAWINGS. IF TREE CLEARING IS NECESSARY FOR ACCESS, SEE "TREE, SHRUB, AND PLANT PROTECTION" NOTES ON SHEET 04 & "TREE PROTECTION BARRICADE" NOTES ON SHEET 34. CONTRACTOR SHALL NOT REMOVE TREES BETWEEN APRIL 15 AND SEPTEMBER 15. ONE (1) WEEK PRIOR TO START TO WORK, CONTRACTOR TO CONTACT CITY FORESTER, 614-645-6640.
  - DURING MOBILIZATION FOR CLEANING AND SHOTCRETE WORK, THE CONTRACTOR WILL CLEAR A WORK AREA NOT LARGER THAN A 20' BY 20' AREA OF UNDERBRUSH FOR EQUIPMENT AND PERSONNEL. EQUIPMENT USED FOR THIS WORK SHALL BE REMOVED FROM THE PROJECT SITE DURING NON-WORKING HOURS. CLEARING OF TREES 12 INCHES AND LARGER IN DIAMETER WILL NEED TO BE COORDINATED WITH CRPD AND CITY FORESTER.
  - DURING MOBILIZATION FOR VENTILATION, THE CONTRACTOR WILL CLEAR A WORK AREA NOT LARGER THAN A 10' BY 10' AREA OF UNDERBRUSH FOR EQUIPMENT AND PERSONNEL. EQUIPMENT USED FOR THIS WORK SHALL BE REMOVED FROM THE PROJECT SITE DURING NON-WORKING HOURS. CLEARING OF TREES 12 INCHES AND LARGER IN DIAMETER WILL NEED TO BE COORDINATED WITH CRPD AND CITY FORESTER.
  - CONTRACTOR SHALL INSTALL TEMPORARY FENCING AROUND OPEN MANHOLES DURING REHABILITATION AND BYPASS PUMPING OPERATIONS.
  - REFER TO SHEETS 07, 08, 09 & 10 FOR PLANS AND PROFILES.
  - SO THAT FLOW FROM THE 108" CONNECTING SEWER DOES NOT ENTER INTO THE PROJECT SEWER, CONTRACTOR MAY INSERT A PLUG AT THE DOWNSTREAM END OF THE BLACKLICK TRUNK. HOWEVER, THERE WILL BE NO TREE CLEARING OR LAND DISTURBANCE TO GAIN ACCESS TO THAT MANHOLE. AFTER THE PLUG IS REMOVED, THE CONTRACTOR SHALL INSTALL SHOTCRETE TO THE CONCRETE SURFACE PER SS-14A.

EASEMENT REFERENCE				REVISIONS		
CITY NO.	COUNTY RECORDER VOL.	PAGE	GRANTOR	NO.	DESCRIPTION	APPROVAL/DATE

**HATCH**

Hatch  
 88 East Broad Street  
 Suite 1900  
 Columbus, Ohio 43215  
 Ph. (614)224-4419 FAX (614)224-4492



SITE ACCESS & OVERALL PLAN

PROJECT TITLE: CITY OF COLUMBUS BLACKLICK CREEK MAIN TRUNK SANITARY SEWER REHABILITATION CIP NO. 650725.100011 CONTRACT A		OWNER: CONTRACTOR: INSPECTOR:	
AGREEMENT	COMPLETED	SCALE: 1" = 120'	SHEET: 06 OF 55
RPD	CKD	ELO	CON. DR.

CITY OF COLUMBUS DEPARTMENT OF PUBLIC UTILITIES DIVISION OF SEWERAGE AND DRAINAGE DIVISION USE ONLY		SCALE: 1" = 120'	SHEET: 06 OF 55
CONTRACT DRAWING NO. CC-19157	RECORD PLAN NO.		

Plotfile: 12/4/2025 11:07 AM

SEE SHEET 6 FOR CONTINUATION



**NOTES:**

- A. ACCESS POINTS ARE SUGGESTED. CONTRACTOR MAY USE ALTERNATIVE ACCESS POINT IF APPROVED. SITE SHALL BE RESTORED TO ORIGINAL CONDITIONS.
- B. THE CONTRACTOR SHALL INCLUDE IN THEIR BID FOR ITEM 623 CONSTRUCTION LAYOUT STAKES THE COST REQUIRED TO SURVEY AND STAKE THE EXISTING EASEMENTS, CITY ROW, PRIVATE PROPERTY LINES AND WETLANDS IN ORDER TO COMPLETE ALL SEWER REHABILITATION WORK AND CONSTRUCT BYPASS LINE. ALSO TO BE INCLUDED IS THE COST TO SURVEY AND STAKE ACCESS ROAD BOUNDARIES AND TREES TO BE REMOVED.
- C. CONTRACTOR SHALL USE THE ACCESS ROUTES IDENTIFIED ON THE DRAWINGS. IF TREE CLEARING IS NECESSARY FOR ACCESS, SEE "TREE, SHRUB, AND PLANT PROTECTION" NOTES ON SHEET 04 & "TREE PROTECTION BARRICADE" NOTES ON SHEET 34. CONTRACTOR SHALL NOT REMOVE TREES BETWEEN APRIL 15 AND SEPTEMBER 15. ONE (1) WEEK PRIOR TO START TO WORK, CONTRACTOR TO CONTACT CITY FORESTER, 614-645-6640.
- D. DURING MOBILIZATION FOR CLEANING, THE CONTRACTOR WILL CLEAR A WORK AREA NOT LARGER THAN A 20' BY 20' AREA OF UNDERBRUSH FOR EQUIPMENT AND PERSONNEL. EQUIPMENT USED FOR THIS WORK SHALL BE REMOVED FROM THE PROJECT SITE DURING NON-WORKING HOURS. CLEARING OF TREES 12 INCHES AND LARGER IN DIAMETER WILL NEED TO BE COORDINATED WITH CRPD AND CITY FORESTER.
- E. DURING MOBILIZATION FOR VENTILATION, THE CONTRACTOR WILL CLEAR A WORK AREA NOT LARGER THAN A 10' BY 10' AREA OF UNDERBRUSH FOR EQUIPMENT AND PERSONNEL. EQUIPMENT USED FOR THIS WORK SHALL BE REMOVED FROM THE PROJECT SITE DURING NON-WORKING HOURS. CLEARING OF TREES 12 INCHES AND LARGER IN DIAMETER WILL NEED TO BE COORDINATED WITH CRPD AND CITY FORESTER.
- F. CONTRACTOR SHALL INSTALL TEMPORARY FENCING AROUND OPEN MANHOLES DURING REHABILITATION AND BYPASS PUMPING OPERATIONS.
- G. REFER TO SHEETS 12, 13, 14 & 15 FOR PLANS AND PROFILES.

Plotfile: 12/14/2025 11:08 AM

EASEMENT REFERENCE				REVISIONS		
CITY NO.	COUNTY RECORDER VOL.	PAGE	GRANTOR	NO.	DESCRIPTION	APPROVAL/DATE
5556-SE	3218	188	COLUMBUS & SOUTHERN OHIO DAN HEUBROK ET AL. JOSEPH T. FERUGSON			
5662-SE	3210	102				
5583-SE	3195	187				

**HATCH**

Hatch  
88 East Broad Street  
Suite 1900  
Columbus, Ohio 43215  
Ph. (614)224-4419 FAX (614)224-4492

SITE ACCESS & OVERALL PLAN

PROJECT TITLE: CITY OF COLUMBUS BLACKLICK CREEK MAIN TRUNK SANITARY SEWER REHABILITATION CIP NO. 650725.100011 CONTRACT A		OWNER: CONTRACTOR: INSPECTOR:	
DIVISION USE ONLY		AGREEMENT COMPLETED	
RPD	CLD	CON	DR

CITY OF COLUMBUS DEPARTMENT OF PUBLIC UTILITIES DIVISION OF SEWERAGE AND DRAINAGE DIVISION USE ONLY		SCALE: 1" = 120'	SHEET: 11 OF 55
CONTRACT DRAWING NO. CC-19157		RECORD PLAN NO.	