Ord No.:0865-2007

Information to be included in all Legislation authorizing entering into a Contract:

1. <u>The names, location by City/State and status of all companies submitting a competitive bid or submitting an RFP or RFSQ.</u>

Name	City/State	Majority/MBE/FBE
Darby Creek Excavating, Inc.	Circleville, Ohio	Majority
Complete General Construction Company	Columbus, Ohio	Majority

2. <u>A full description of all work to be performed including a full description of work to be performed during any known phasing of the contract.</u>

The project provides for general rehabilitation of the area distribution system and includes construction of new water mains, abandoning existing water mains, and transferring water services in the East Side area. The purpose of the project is to improve flow and water quality and replace water mains that require repeated regular maintenance. Work on Atcheson Street will include construction of a 6" water main from the first alley west of St. Clair Avenue to the first alley west of St. Clair Avenue, abandoning the existing 1" and 1 1/2" mains, and transferring water services. Along Joyce Avenue service taps will be transferred from the existing 8" main to an existing 16" main. The existing 8" main will be abandoned. Work on Leonard Avenue will include the construction of a 12" main from Fifth Avenue to Woodland Avenue and abandoning the existing 8" main. Work on Delbert Road will include the construction of a 6" main, abandoning the existing 2" main, and transferring water services. Along Seventeenth Avenue service taps will be transferred from the existing 8" main to an existing 16" main. The existing 8" main will be abandoned. Along Woodland Avenue service taps will be transferred from the existing 6" and 8" mains to an existing 16" main. The existing 6" and 8" mains will be abandoned. Work on Werling Place will include construction of a 6" water main, abandoning the existing 2" main, and transferring water services.

3. <u>A narrative timeline for the contract including a beginning date, beginning and ending dates for known phases of the contract and a projected ending date.</u>

The contractor has 270 calendar days after the Notice to Proceed to complete all work.

4. <u>An estimate of the full estimated cost of the Contract including a separate estimate of any and all phases or proposed future contract modifications.</u>

Construction:	\$1,715,969.65
Construction Administration:	<u>\$ 267,675.00</u>
Total:	\$1,983,644.65