


"CITY OF COLUMBUS 2025 UTC QUOTATION"

THIS QUOTATION IS VALID FOR 90 DAYS

Please sign and return to confirm order

X _____



QUOTE

Name	Ryan Conley				Date:	6/13/2025	
Company	City of Columbus Division of Water				Sales		
Address	910 Dublin Rrd				Rep:	Rick Tschiggfrie	
City	Columbus	State	OH		Order		
Phone	614-645-8276	Mobile	614-724-0128		Date:		
Email	reconley@columbus.gov				PO #:		
Chassis Information:	2025	Make Cab	Ford Regular Cab	WB CA/CT	84" CA	Model Engine GVWR	F550 7.3L Gas 19,500#

Qty	Description	Unit Price	Total
1	Stellar 1302E Commercial Fleet Tire Service Truck 2025 Ford Cab Chassis with a 84" Cab-To-Axle, constructed as follows: *13' Long x 8' Wide Aluminum Body *(2) 64" High Front Vertical Compartments - 22" Deep x 26" Wide *Full Height Removable Rear Gate Between Vertical Compartments *(2) Underbody Boxes Located at Curbside & Streetside Rear 19"H x 38"W x 22" D *(2) Underbody Boxes Located at Curbside & Streetside Front 19"H x 29"W x 22" D *Body Painted White - Single Stage - Non-Metallic *Underbody Tool Box Panel - Installed *Lid for Hydraulic Air Compressor *(2) Bar Truck Tire Safety Inflation Cage - Stows on Body Deck *Aluminum Folding Step Installed *Plastic Tray Package (4) 5" W Trays & (6) 3.5" Trays for Vertical Compartments *HD Drawer Set in CS1V Hanging from Top (2) 3" Drawers - 18" W x 18" D *15-Pin Socket Rack Installed in CS1V *DRI-DEK Installed on ALL Shelving & Compartment Floors *(6) Adjustable Shelves *21" Sign Board Panel Extension to Make a 43" Sign Panel *Adjustable Horizontal Tire Racks - 3 Aluminum Shoring Bars Cut to Fit *Electrical Control Kit Utilizing Ford Upfitter Switches *Plus additional standard Stellar features <u>American Eagle 65R Air Compressor</u> *65 CFM @ 100 PSI Rotary Screw Air Compressor - 100% Continuous-DUTY *Oil Injected Rotary Screw Air End is Belt Driven by a Hydraulic Motor *Integral Cooler for Both Compressor Oil & Truck's Hydraulic Oil *26 Gallon Hydraulic Reservoir - 22 Gallon Air Tank *Steel Base Plate with Filter - Unit is Painted Single Stage White (Page # 1 of 2 - Continued Next Page)		
This order not binding until approved by a company official. All quotations & delivery promises made and orders accepted subject to delays caused by fire, accident, strike or other causes beyond our control. Deliveries delayed by any of the above conditions shall not constitute cause for cancellation of this order. Price subject to change without notice.		SubTotal	
		Freight	
		Taxes	"Exempt"
		TOTAL	

"CITY OF COLUMBUS 2025 UTC QUOTATION"

THIS QUOTATION IS VALID FOR 30 DAYS

Please sign and return to confirm order

X _____



QUOTE

Qty	Description	Unit Price	Total
	<u>HYDRAULIC SYSTEM:</u> *PTO for Ford 10-Speed Automatic Transmission *Single Section Hydraulic Pump *All Necessary Hose & Fittings <u>AIR SYSTEM:</u> *1/2" X 50' Reel Craft Dual Pedestal Hose Reel - Artic Grade *1/2" x 50' Reel Craft Dual Pedestal Hose Reel - Artic Grade *1/2" FLR with Safety Air Dump Valve - Installed Curbside *20' OTR Inflation/Deflation Hose Kit with Quick Release Coupler for Evacuation *Includes Muffler, Small & Large Bore Core Ejectors & 1/4 Turn Ball Valve *Rotary Air Gauge for Checking Tire Pressure *(2) Auxiliary Air Outlets - (1) 3/8" & (1) 1/2" <u>TOMMYGATE 2000# ALUMINUM RAILGATE:</u> *2000# Capacity Liftgate with Aluminum Frame - Recessed Lights *Folding Side Rail & Tire Stop *1-1/2" Aluminum Angle Welded on Aluminum Platform <u>LIGHTING:</u> *LED Compartment Light Kit with Electric Control Switch *(4) LED Worklights Installed *Streamlight Stinger Switchblade LED Work Light with J-Hook, Magnetic Base & UV Light for Leak Detection - Includes Charger *Whelen 54" EDGE Lightbar with CCP9 Controller Installed in Cab *Lightbar per City of Columbus Contract Bid - Includes Power Control Center *(4) Whelen Micron Super LED Strobes Mounted at Rear of Body *(2) Whelen Micron Super LED Strobes Mounted on Front Grill *Electric Back-Up Alarm Installed *Installation of Chassis Supplied Back-Up Camera <u>MISC:</u> *Removable Angle in Floor - (1st) 32" Back From Front of Body (2nd) 72" Back *Galvanized E-Track Riveted to Each Side of Cargo Walls Full Length 1/2 Way Up *(3) Shoring Bars Cut to Width to Fit E-Track *Heavy Duty Rubber Mudflaps Installed Rear of Axle *Ultimate Power CSW1220 2000 Watt Power Inverter Installed in Curbside Rear *Interstate Battery Group 31 GEL AGM Battery with Battery Box - Curbside Rear *Battery Isolator Installed to Protect OEM Truck Batteries *Ultimate Power Cabling Kits from OEM Battery to Auxiliary to Inverter ~ Total Installed Price Each Thank You - Rick Tschiggfrie - fob: City of Columbus 12 Weeks Build Time on Tire Truck from Stellar (Page # 2 of 2 - End of Quotation)		\$ 86,995.00
<i>This order not binding until approved by a company official. All quotations & delivery promises made and orders accepted subject to delays caused by fire, accident, strike or other causes beyond our control. Deliveries delayed by any of the conditions shall not constitute cause for cancellation of this order. Price subject to change without notice.</i>		SubTotal	\$ 86,995.00
		Freight	
		Taxes	"Exempt"
		TOTAL	\$ 86,995.00