Sutphen Corporation 6450 Eiterman Rd Dublin, Ohio 43016 tschafer@heritagefireequipment. com



ADDRESS

John King City of Columbus 3675 Parsons Avenue Ohio

Columbus, OH 43207

SHIP TO

John King City of Columbus 3675 Parsons Avenue Columbus, Ohio 43207 Estimate 2019-424

DATE 10/29/2019

HS NUMBER

3963

ITEM/DESCRIPTION	QTY	RATE	AMOUNT
10114608 Bucket, Sutphen, SPH100	1	32,284.05	32,284.05
10087877 Bucket Mount, Sutphen, SPH100, Left Side	1	1,300.72	1,300.72
10087878 Bucket Mount, Sutphen, SPH100, Right Side	1	1,300.72	1,300.72
10109992 Yoke, Sutphen, SPH	1	6,650.36	6,650.36
10040216 ASSY parapet ladder, Supthen SPH 100	1	2,131.51	2,131.51
10039872 ARM stokes basket support, SPH 100, Supthen	2	214.67	429.34
10039871 SPACER bucket w/stokes arms, SPH 100	2	19.65	39.30
10063859 TAG stokes arm capacity, SPH100	2	31.24	62.48
10039927 CAP end stop tube, SPH100	4	30.99	123.96
10066214 SURRORT Arm Washer-Stokes, SPH100	4	5.29	21.16
10020721 SPRING LATCH SINGLE POINT, SPH100	2	20.84	41.68
10035859 ANGLE ALUM 6061 T6 1" x 1" x .125"x 300"	10	1.24	12.40
10039839 LATCH support arm, SPH100	2	14.45	28.90
10039999 D-Ring Tie-off 1 w x 1", SPH100, SP95	4	79.66	318.64

ITEM/DESCRIPTION	QTY	RATE	AMOUNT
10039836 PLATE stokes arms 100SPH BUCKET INNER	2	24.92	49.84
10039837 PLATE stokes arms 100SPH BUCKET OUTER	2	31.86	63.72
10039838 SPACER support arm, SPH100	1	59.42	59.42
10066239 Handrail, Knurled Stainless Formed, 30"	4	169.82	679.28
10066234 HANDRAIL platform, Grab Bar, Front Accesse From Body	1	527.89	527.89
10003087 LOGO, Sutphen Nameplate SS 7.875" x 3.5" x .090	1	65.28	65.28
10053085 Flexmaster Joint, Marman, 4" P, SP110	1	253.04	253.04
Service Labor Removal of Bucket and Yoke From Ladder -disassemble bucket from yoke -disassemble yoke from ladder -disassemble water way from yoke -disassemble wiring and hydraulic bucket from yoke	10	116.45	1,164.50
Service Labor Disassemble Bucket Components -disassemble useable bucket components -save and inventory all undamaged components	25	116.45	2,911.25
Service Labor Assemble Bucket Components in New Bucket -reinstall all undamaged components of the bucket -stokes arms - parapet ladder -function test -D-Rings -handrails -lighting -bucket weldment left and right -left and right monitor and waterway - hydraulics	75	116.45	8,733.75
Service Labor Waterway "Y" (Damaged) -remove from 5th section and install new	6	116.45	698.70
Service Labor Swivel (Damaged) -install new swivel on the yoke	3	116.45	349.35
10068914 WELDMENT UPPER W/WAY TUBE "Y" 100-5SEC MAGNUM	1	1,322.34	1,322.34
10068915 PIPE UPPER W/W RT HORZ SPH100	1	402.04	402.04
10074573 ASSY Swivel W/90 Deg Elbow 3"	1	1,329.44	1,329.44
10065197 COUPLING Groovelock / Victaulic 3" Alum	2	364.31	728.62

ITEM/DESCRIPTION	QTY	RATE	AMOUNT
10065198 COUPLING Groovelock / Victaulic 4" Alum	1	443.63	443.63
Service Labor Install New Yoke and Bucket on Aerial Boom	10	116.45	1,164.50
Graphics Reinstall Provide and reinstall graphics as below -bucket door decals -warning tags	1	850.00	850.00
Shop Supplies-Misc Shop Supplies-Misc nut and bolts hucks hydraulic lines fittings	1	489.62	489.62
Ladder Test A 3rd part ladder test shall be provide. Documentation shall be provided of the test.	1	875.00	875.00
Service Labor 5th Section Ladder Inspection ** Once the bucket and the yoke are removed the tip of the 5th section will need to be inspected to ensure the section was not damaged in the wreck. If additional damage is found the quote with be updated.	1	116.45	116.45
Service Estimate Disclaimer The prices listed on this estimate are good for 30 days. This is an estimate of the parts and labor necessary to complete the repair. As so, the final price may vary. The final price may vary up to 10% above the estimate without additional customer approval to proceed. The apparatus owner is responsible for transportation and insurance on the vehicle to and from Heritage Fire Equipment.	1	0.00	0.00

BR 17352 HS3963

Quote is valid for 30 days and does not include shipping.

TOTAL \$68,022.88	
-------------------	--

Accepted By Accepted Date